

**CITY OF PENTICTON**  
**FAIRVIEW SANITARY LIFT STATION REVIEW**  
**TECHNICAL MEMORANDUM**  
**9 MAY 2011**

The Fairview Lift Station is located at the corner of Fairview Road and Industrial Avenue and services a small area. The station is fitted with 2 Flygt CP 3085.182 MT, 3 HP pumps and discharges into a 100 mm Ø asbestos cement pipe pumping to a manhole at Huth Road, 260 m away. The station's internal piping and the AC forcemain has failed and needs replacement.

The City requested Focus to review the station pumping capacity and its ability to pump into the adjacent 450 mm Ø PVC Lee Avenue Pump Station forcemain, thereby abandoning the 100 mm AC forcemain.

The following is a brief design memorandum on the proposed upgrade as depicted on Dwg. M01 attached.

A. Pump Capacity

Existing pumps are 3 HP Flygt pumps. In order for the pumps to discharge to the Lee Avenue 450 mm forcemain, they will have to match the Hydraulic Grade Line (HGL) in the main under 3 scenarios:

1. with Lee Avenue Pump Station not operating;
2. with Lee Avenue Pump Station discharging 160 l/s; or
3. with Lee Avenue Pump Station discharging 160 l/s in conjunction with a future 65 l/s discharge from Penticton Indian Band.

In each case, the static head, assuming an average water level in the wet well of 339.63 m, to be met will be:

1. Water level in AWTP (344.82 m) minus 339.62 m above = 5.2 m
2. HGL at Fairview LS with Lee PS @ 160 l/s less the 339.63 m above = 345.85 – 339.63 or 6.22 m.
3. HGL at Fairview LS with Lee PS @ 160 l/s and 65 l/s from P.I.B. less Fairview water level = 346.75 – 339.62 or 7.12 m.

In addition to the above, the HGL for each scenario will have the friction head through a new 100 mm Ø SS pipe added and this is estimated to be 0.6 m (c = 100, length 4.3 m, check valve, @ Q = 20 l/s).

The attached Sketch 1 shows the pump and system head curve for each scenario. (Note: System Curve #4 reflects the existing system/head curve for the 3 HP pumps pumping to Huth Road.)

As can be seen from Sketch 1, all pump operating points are on the pump curve. Existing station flow is approximately 9 l/s and upgraded flow will be approximately 20 l/s through the shorter forcemain.

Based on the above analysis, the existing pumps are suitable for the upgraded service. We did a calculation of wet well operating capacity for pump starts. Maximum pump starts occur when station inflow equals half the pump capacity. Assuming a 600 mm operating water level (stop to start), we estimate the maximum pump starts to be 6 starts/hr/pump.

This exceeds bylaw requirements of 4 starts/hr/pump but it will be less than the manufacturer's recommendation of 15 starts/hr/pump.

#### B. Temporary Bypass Pumping

The City intends using a 0.5 HP submersible sewage pump for temporary bypass pumping during construction. This pump will be located in adjacent inflow manhole and pumped through a temporary connection to the 450 mm Lee forcemain.

Elevation of bypass MH sump = 340.38 m

Assume: Average water level in MH is 400 mm depth  
i.e. water level =  $340.38 + 0.4 = 340.78$  m

Assume: Lee pumps operating, i.e. HGL = 345.85  
Then static =  $345.5 - 340.75 = 5.1$  m (16 ft)

Friction: 4 m, 75 mm Ø, Q = 10 l/s, H = 0.5 m

TDH =  $5.1 + 0.5 = 5.6$  m (18 ft)

Attached Sketch 2 illustrates the pump/system curve for this application. As can be seen, operating point is 80gpm @ 18 ft with 2 Lee pumps operating and 110gpm at 13ft when the Lee pumps are not running. Both points are on the pump curve. We are not sure what the station inflow is but the 80 to 110 gpm is probably adequate. This will have to be monitored though.


C. Conclusion


Based on the above analysis, the Fairview Lift Station can be upgraded to discharge to the 450 mm Lee Avenue PS forcemain. Dwg. M01 reflects to upgrade proposal.



Rob Fortuin, P. Eng.  
Project Manager  
[rob.fortuin@focus.ca](mailto:rob.fortuin@focus.ca)



				PERFORMANCE CURVE				PRODUCT CP3085.182		TYPE MT			
DATE 2005-01-31		PROJECT						CURVE NO 63-434-00-5330		ISSUE 5			
MOTOR COS PHI MOTOR EFFICIENCY GEAR EFFICIENCY		1/1-LOAD		3/4-LOAD		1/2-LOAD		MOTOR SHAFT POWER ..... 3      hp STARTING CURRENT ... 53      A RATED CURRENT ... 9.6      A RATED SPEED ..... 1700      rpm TOT.MOM.OF INERTIA ... 0.034      kgm2 NO. OF BLADES 1		IMPELLER DIAMETER 163 mm			
		0.83		0.77		0.66				MOTORTYPE 15-10-4AL		STATOR 27Y	
		77.5 %		78.5 %		76.5 %				REV 12			
COMMENTS		---		---		---		FREQ. 60 Hz		PHASES 3			
		---		---		---		VOLTAGE 208 V		POLES 4			
		---		---		---		GEARTYPE ---		RATIO ---			
		INLET/OUTLET - / 80 mm											
		IMP. THROUGHLET 76 mm											



FLYPS2.19 (20021016)

(NPSHR) = (NPSH3) + margins

Performance with clear water and rating data at 40 °C




CURVE



## SWM Series

1/2 & 1 hp Submersible Sewage Pump, 2" solids



### Construction

Motor Housing	Epoxy Coated Cast Iron
Impeller Material	Cast Iron
Impeller Type	Non-clog
Volute	Epoxy Coated Cast Iron
Power Cord	SJTW SJOW (Others)
Mechanical Shaft Seal	Nitrile Parts, Stainless Steel, Carbon & Ceramic Faces
Fasteners	Stainless Steel
Shaft	416 Stainless Steel
Bearings	Ball Bearings




### Specifications

MODEL NO.	ITEM NO.	HP	VOLTS	SFA	PHASE	TOTAL HEAD IN FEET								SHUT-OFF		SOLIDS HAN- DLING	WEIGHT (LBS.)	CORD LENGTH	RPM
						5	10	15	20	25	30	35	FEET	PSI					
						CAPACITIES IN U.S. GPM													
SWM-52	511213	½	115	11.6	1	135	90	56	14	-	-	-	23	10	2"	57	20'	1,750	
SWM-52-AF	511214	½	115	11.6	1	135	90	56	14	-	-	-	23	10	2"	59	20'	1,750	
SWM-52H	511215	½	115	11.6	1	-	128	97	68	32	-	-	29	12.6	2"	58	30'	3,450	
SWM-52H-AF	511216	½	115	11.6	1	-	128	97	68	32	-	-	29	12.6	2"	60	30'	3,450	
SWM-52H	511217	½	208-230	11.6	1	-	128	97	68	32	-	-	29	12.6	2"	58	30'	3,450	
SWM-52-AF	511218	½	208-230	11.6	1	-	128	97	68	32	-	-	29	12.6	2"	60	30'	3,450	
SWM-102	514234	1	208-230	10.7	1	-	168	144	118	85	46	-	37	16.1	2"	62	20'	1,750	
SWM-102H-AF	514235	1	208-230	10.7	1	-	168	144	118	85	46	-	37	16.1	2"	64	20'	1,750	
SWM-102	514236	1	208-230	4.58	3	-	168	144	118	85	46	-	37	16.1	2"	63	20'	1,750	
SWM-102	514237	1	460	2.15	3	-	168	144	118	85	46	-	37	16.1	2"	63	20'	1,750	
SWM-102H	514238	1	230	13.3	1	-	190	170	148	124	100	74	48	20.9	2"	61	30'	3,450	
SWM-102H-AF	514239	1	230	13.3	1	-	190	170	148	124	100	74	48	20.9	2"	63	30'	3,450	


Note: Manual models do not include float switch. Automatic models include float switch.

SKETCH 2.





\* - DIMENSIONS WITH ASTERISK TO BE VERIFIED IN FIELD



PIPING SCHEDULE ITEMS No. 1 AND No. 2  
TO BE INSTALLED BY CITY OF PENTICTON

ALL PIPING SHALL BE CLASS 304L  
SCHEDULE 10 STAINLESS STEEL  
ALL FLANGES SHALL BE CLASS 150  
STAINLESS STEEL

ANGLE OF FABRICATED BEND IN  
PIPING SCHEDULE ITEM No. 8 IS  
APPROXIMATELY 27 DEGREES



#### NOTES:

- ALL PIPING THROUGH WALLS, SLABS OR OTHER CONCRETE STRUCTURES SHALL BE WATER TIGHT AND SHALL CONTAIN A PUDDLE FLANGE WELDED TO THE PIPE.
- CONTRACTOR IS TO CONFIRM ALL DIMENSIONS AND PIPING SCHEDULE ITEMS, QUANTITIES AND JOINTS.
- ALL PIPING SHALL BE SUPPORTED FROM WALLS, FLOOR SLABS AND CEILINGS FOR THRUST RESTRAINT AND SUPPORT OF PIPE AND/OR FITTINGS. USE GRINNEL OR EQUIVALENT PIPE SUPPORTS.
- ALL PIPE SUPPORTS, INSERTS, BOLTS, NUTS AND OTHER MISCELLANEOUS METALS TO BE STAINLESS STEEL.
- SUBMIT SHOP DRAWINGS FOR REVIEW FOR ALL EQUIPMENT.

#### SCOPE OF WORK:

- WET WELL TO BE ISOLATED BY CITY WITH BYPASS PUMPING BY CITY.
- CITY WILL DO ALL EXCAVATION, BACKFILLING, SITE RESTORATION AND SUPPLY/INSTALL HOT TAP AND GATE VALVE.
- CONTRACTOR TO DO ALL STATION INTERNAL PIPEWORK (INCLUDING REMOVAL OF EXISTING) AND ALL WORKS TO TIE TO CITY INSTALLED GATE VALVE, INCLUDING MANHOLE.
- CONTRACTOR TO COMPLY WITH CONFINED SPACE ENTRY REGULATIONS.
- EXCAVATION TO BE FENCED BY CONTRACTOR AND SECURED OVERNIGHT.

TO BE INSTALLED BY  
CITY OF PENTICTON



PIPING SCHEDULE (CONTRACTOR TO CONFIRM AND INCLUDE ALL FITTINGS NOT LISTED)			
No.	SIZE	No. REQD	DESCRIPTION
1	450x100	1	STAINLESS STEEL TAPPING SLEEVE - ROBAR MODEL 6606 FOR C905, DR41 PVC PIPE
2	100	1	GATE VALVE - NRS, S.S. BODY, BRONZE MOUNTED, SOLID WEDGE c/w V.B. AND RISER
3	100	1	FLxFL 45° BEND - STAINLESS STEEL c/w S.S. 150 lb. FLANGES
4	100	1	FLxFL SPOOL - STAINLESS STEEL c/w S.S. 150 lb. FLANGES - LENGTH TO SUIT
5	100	1	MAGNETIC FLOWMETER - SITRANS F M MAG 5100 W c/w MAG 5000, IP67/NEMA 4X/6, POLYAMID ENCLOSURE, WITH DISPLAY, 115-230V AC 50/60 HZ, AND USM POTTING KIT
6	100	1	FLxPE SPOOL - STAINLESS STEEL c/w S.S. 150 lb. FLANGE - LENGTH TO SUIT
7	100	1	ADAPTOR COUPLING - STAINLESS STEEL - ROBAR MODEL 1736AS
8	100	1	FLxPE SPOOL - STAINLESS STEEL c/w S.S. 150 lb. FLANGE, WELDED BEND (ANGLE TO BE DETERMINED IN THE FIELD) - LENGTH TO SUIT (ANGLE ± 27°)
9	100	1	FLxPE SPOOL - STAINLESS STEEL c/w S.S. 150 lb. FLANGE AND PUDDLE FLANGE - LENGTH TO SUIT
10	100	3	ADAPTOR COUPLING - TEEKAY AXILOCK-S
11	100	1	WELDxPE SPOOL - STAINLESS STEEL - LENGTH TO SUIT
12	100x100x100	1	WELDxWELD TEE - STAINLESS STEEL - LENGTH TO SUIT
13	100	2	WELDxWELD SPOOL - STAINLESS STEEL - LENGTH TO SUIT
14	100	2	FLxFL 90° BEND - STAINLESS STEEL c/w S.S. 150 lb. FLANGES
15	100	2	FLxFL CHECK VALVE - FLYGT TYPE 5087 HDL CHECK VALVE
16	100	4	FLxPE SPOOL - STAINLESS STEEL c/w S.S. 150 lb. FLANGES - LENGTH TO SUIT
17	1050	1	MANHOLE c/w BASE, RISERS, LADDER RUNGS, LID, GRADE RING AND FRAME AND COVER - MAKE WATER TIGHT
18	-	-	-
19	-	-	-
20	-	1	ADJUSTABLE PIPE SUPPORT - GRINNEL OR APPROVED EQUAL

MAGNETIC FLOWMETER : SUPPLIER E.B. HORSEMAN & SON  
#1 - 13055 80th AVENUE  
SURREY, B.C. V3W 3B1  
CONTACT : JOHN CINDRIC  
PHONE : 604.596.7111  
CELL : 604.501.2321  
TOLL FREE : 1.800.242.5863  
E-MAIL : jcindric@ebhorseman.com

THIS DRAWING AND DESIGN IS PROTECTED UNDER COPYRIGHT AND ANY USE, REPRODUCTION OR REVISION IS STRICTLY PROHIBITED WITHOUT THE WRITTEN PERMISSION OF FOCUS CORPORATION.  
THESE DRAWINGS SHOULD NOT BE SCALED. IF BEING USED FOR CONSTRUCTION, THE CONTRACTOR MUST CHECK AND VERIFY ALL DIMENSIONS AND SHALL REPORT ANY DISCREPANCIES OR OMISSIONS PRIOR TO COMMENCEMENT OF ANY WORK.

"NOT FOR CONSTRUCTION"  
PRELIMINARY 2011/05/03

DATE	REV	DESCRIPTION	BY	APPR.	DATE	REV	DESCRIPTION	BY	APPR.
2011/05/09	A	REVISIONS AS PER CITY COMMENTS	DEM	RBF					

SCALE AS NOTED  
DATE 2011/05/03  
APPROVED RBF  
DESIGN BY RBF  
DRAWN BY DEM  
CHECKED BY RBF

**FOCUS**

ENGINEERING • PLANNING • GEOMATICS  
702-1708 DOLPHIN AVENUE, KELOWNA, BC, V1Y 9S4  
PHONE 250.980.5500 FAX 250.980.5511

CITY OF PENTICTON  
FAIRVIEW PUMP STATION UPGRADE - 2011  
MECHANICAL - PIPING PLAN

REV. No. A  
OFFICE No. 061200061  
DRAWING No. M01